



NI Water Telemetry

Date: 2006—2008

Contract Value: £800,000

Contract Summary

Installation and maintenance of telemetry at approximately 200 Waste Water Treatment Works throughout N. Ireland

Contract Specifications

- Manufacture, Supply and installation of MCC Panel and Pump Sets
- Manufacture, supply and installation of Kiosks & Telemetry Outstation and Radio.
- Disconnection and removal of existing redundant equipment as per site requirements.
- Installation of 1 No GRP Kiosk/site
- Manufacture, supply, delivery, off-loading, installation, interconnection and commissioning of new MCC Panel (direct online or star delta as required) complete with ultrasonic level controller.
- Installation of 1 No Serck telemetry outstation PX24-5E
- Connection of Telemetry outstation radio using MPT 1411 radio communications.
- Store and forward Telemetry outstation information and use of deregulated frequencies.
- Connection of outstation to GSM and Satellite communications equipment
- Site Commissioning

Client

NI Water, 34 College St., Belfast, BT61 6DR

